Att Mr George Naguib
m/s Feltex Carpets Pty Ltd,
8 Scotland St, Braybrook Vic 3019

TEST REPORT No. 104020

LABORATORY REF: P104020

CUSTOMER REFERENCE

VERSATILE

Sample description as provided by customer Order No. **GN**

Mass/unit area **18** oz/yd² **/** g/m² Pile Fibre Content **100% SOLUTION DYED NYLON**

Construction Details **Tufted** Secondary Backing **Jute** Colour **GREY**

Style **LOOP** Pile Height **/** mm

TEST METHOD AS/ISO 9239.1 2003 Reaction To Fire Tests For Floorings Part 1 Determination of the Burning Behaviour Using a Radiant Heat Source. *As required by specification C1.10a of the Building Code of Australia.*

Tested in accordance with the Carpet Institute Code of Practice for AS/ISO 9239 Testing Version 10 / 0805.

The test values relate to the behaviour of the test specimens of a product under the particular conditions of the test, they are not intended to be the sole criterion for assessing the potential fire hazard of the product in use. Clause 9 of AS/ISO 9239 Part 1.

Conditioning as specified in BS EN 13238.2001

Sample submitted Date **Feb 2010** Test Date **29/3/2010**

ASSEMBLY SYSTEM: DOUBLE BOND (DOUBLE STICK) (Details Below).

The underlay used was DUNLOP ULTRALAY it was adhered to the substrate using DUNLOP PRIME & PEEL adhesive. The floor covering was adhered to the underlay using DUNLOP ULTRA BOND adhesive.

Substrate : Non-combustible
Substrate – 6mm Fibre Reinforced Cement Board to simulate a Non-Combustible Flooring.
Sample Cleaned as Specified in ISO 11379.1997. The Holding Torque on Specimen Frame was 2Nm.

Initial Test Specimen 1 Length Direction Critical Radiant Flux **1.3** kW/m²
Specimen 1 Width Direction Critical Radiant Flux **1.3** kW/m²
Full tests carried out in the **Length** Direction

SPECIMEN	Length #1	Length #2	Length #3	Mean
Critical Radiant Flux (kW/m²)	1.3	1.2	1.2	1.2
Smoke Development Rate (%.min)	121	328	295	248

The values quoted below are as required by Specification C1.10a Fire Hazard Properties (Floors) of the Building Code of Australia. The Critical Radiant Flux quoted is the value at Flame-Out/Extinguishment (BCA General Provisions A1.1).

MEAN CRITICAL RADIANT FLUX 1.2 kW/m²

MEAN SMOKE DEVELOPMENT RATE 248 %.min

OBSERVATIONS **The samples shrunk away from the heat sourcee ,ignited then burnt.**

NATA ACCREDITED FOR TECHNICAL COMPETENCE

M. B. Webb
Technical Manager

DATE: 29/3/2010

Measurement Science & Technology No. 15393
This document is issued in accordance with NATA's accreditation requirements.

PAGE 1 of 2

This Page (1) has been designed to show the values required under Specification C1.10a Fire Hazard Properties (Floors) of the Building Code of Australia.

The values on Page 2 have no relevance to the Code.

1004 04 09

APL Australia Pty Ltd
5 Carinish Rd, Oakleigh South
Victoria 3167 Australia

Telephone: 03 9543 1618
Facsimile: 03 9562 1818
Mobile: 0411 039 088

Email: apl@aplaustralia.com.au
Web: www.aplaustralia.com.au
ABN 69 468 849 319

TIME FOR EACH SPECIMEN TO REACH EACH MARKER IN SECONDS

Specimen	50	60	110	160	210	260	310	360	410	460	510	560	610	660	710	760	810	860
1	196	198	213	236	257	273	298	318	353	409	520	621	1119	1372	1873	2041	/	
2	165	167	220	228	243	270	299	318	346	370	459	664	1196	1285	1903	2436	2944	
3	1810	183	248	248	252	271	295	314	350	434	529	637	899	1260	1696	2057	/	

TESTS	**SMOKE PRODUCTION**		**BURNING CHARACTERISTICS**		
Specimen	**Maximum Light Attenuation (%)**	**Smoke Development Rate (%.min)**	**Burn Length (mm) at Flame Out/ Extinguishment**	**Time To Burn Out (s)**	Critical Heat Flux at 30min (kW/m²)*
Initial Test: **Width**	**78**	**302**	**790**	**3,160**	1.7*
Specimen Tests: **Length**					
1	79	121	800	2,472	1.7*
2	78	328	820	3,175	1.7*
3	80	295	809	2,449	1.7*
Mean	79	248	810	2,699	1.7*

NATA
ACCREDITED FOR TECHNICAL COMPETENCE

M. B. Webb
Technical Manager

DATE: 29/3/2010

Measurement Science
& Technology No. 15393
This document is issued in accordance with NATA's accreditation requirements.

The laboratory does not allow the use of this page of the report without the use of page 1.
This page alone has no validity under specification C1.10a Fire Hazard Properties (Floors) of the Building Code of Australia.
* Critical Heat Flux at 30min has no relevance under the Building Code of Australia which demands Heat Flux measurement at Flame Out/Extinguishment (BCA General Provisions A1.1).
2004 04 09 35293 29 March 2010

APL Australia Pty Ltd
5 Carinish Rd, Oakleigh South
Victoria 3167 Australia

Telephone: 03 9543 1618
Facsimile: 03 9562 1818
Mobile: 0411 039 088

Email: apl@aplaustralia.com.au
Web: www.aplaustralia.com.au
ABN 69 468 849 319